

concrete pipe & precast journal

FALL 2021



Plant Tours

Let CCPPA organize a plant tour for your team. Member facilities produce a wide range of concrete pipe and precast products. Our tours address:

- Quality Control
- Manufacturing QA Programs
- Dry cast manufacturing
- Wet cast manufacturing
- Three-edge bearing strength testing
- Hydrostatic testing
- Product examination

Call 519.489.4488 or email resources@ccppa.ca to book your tour today.



Lunch & Learns

Educate your staff on topics such as *Protecting Yourself as a Gravity Pipe Designer*, the *Marston Spangler Method or PipePac Software* with a free Lunch & Learn from CCPPA. You pick the topic and invite key staff, and we bring lunch and a 60-minute presentation — at no charge to you.

Call 519.489.4488 or email resources@ccppa.ca to book your Lunch & Learn today.



In This Issue...

P3 | Precon Supplies Lined Vaults for Twin Sanitary Sewer Upgrade in Calgary

P4 | Forterra Provides Microtunneling Solution for Twin Culvert Replacement

P4 | Stanley Park's Beaver Lake: Custom Box Culverts with Fish Ladders to Improve Ecosystem

P5 | Proform Utilises 3D Modeling, of Large Box Culvert Project: City of Calgary

P6 | Cast in Collaboration

Concrete Pipe Greatly Reduces Excess Soil Challenges

Paul Imm, P.Eng.
Director of Engineering
Forterra Pipe & Precast, Ltd.

In December 2019, the province of Ontario announced that they were introducing a new regulation under the Environmental Protection Act that would result in a reduction in construction costs by making it easier to reuse excess soil generated during construction activities. This will ultimately minimize waste and provide clear rules for managing and reusing excess soils.

The Ontario Ministry of the Environment, Conservation and Parks (MECP) estimates that 25 million cubic metres of excess soil is generated in Ontario every year. While most of this excess soil could be reused safely, it is often moved off-site because it can't or won't be reused at the development site. The MECP implemented the On-Site and Excess Soil Management Regulation (O.Reg. 406/19) on January 1, 2021 to help reduce negative impacts and costs from improper management of excess soil such as:

- Noise and dust
- Truck traffic and road damage
- Erosion and drainage
- Other social, economic, health and environmental concerns.

While MECP has created best practice guides and calculation tools to assist with the excess soil



regulation, the Greater Toronto Sewer and Watermain Contractors Association (GTSWCA) retained WSP Canada to help its members identify opportunities for the effective and beneficial use of both excavated soils and recycled materials for buried pipe construction. A report, published in August 2020, reveals that the production of aggregate in Ontario is approximately 45 to 90 million cubic metres annually, with a growing demand over the next 25 years at unsustainable levels and an enormous carbon footprint associated with the mining and transportation of new aggregate sources.

The Executive Summary of the GTSWCA-WSP identifies the following issues associated with disposing of excess soils:

continued on page 2



Return undeliverable Canadian addresses to:
Canadian Concrete Pipe And Precast Association, 447 Frederick St, Suite 200, Kitchener, Ontario N2H 2P4



Concrete Pipe Greatly Reduces Excess Soil Challenges

continued from page 1


- Extra costs on many infrastructure projects
- Environmental impacts related to virgin aggregate extraction in existing agricultural and protected areas
- Additional trucking distances to import virgin aggregate materials
- Significantly larger carbon footprint related to the above issues.

The GTSWCA-WSP report also proposes the following key areas of recommendations:

- Performance requirements to ensure suitable performance of serviceability of engineered fill
- Compaction methods to improve engineering properties of fill
- Current uses and specifications on backfill material and compaction, and the need to explore reforms for more viable options
- Guidelines to help assess the suitability of excavated native soils as trench backfill
- Benefits of using recycled aggregates (or blended with RAP) as trench backfill for all weather placement
- Recommendations for restructuring public works tenders to allow for greater use of native soils and recycled materials for backfill.

Many years prior to this new MECP excess soil regulation, the Ontario Concrete Pipe Association published an article in the Fall 2013 edition Concrete Pipe Journal titled, *Concrete Pipe Installed with Recycled Aggregate: Good for the Environment and Good for the Economy*, which considers the opportunities to use recycled aggregate as a backfill material for concrete pipe, which flexible plastic or corrugated steel pipe products do not allow. The same claims can be made about using select native soils to install concrete pipe.

Ontario Provincial Standard Specifications (OPSS.PROV) 401 used by the Ministry of Transportation, Construction Specification for Trenching, Backfilling and Compacting, clearly identifies the differences between the installation requirements of a rigid concrete pipe and flexible plastic or metal pipe for sanitary and storm sewers, pipe culverts, subdrains, forcemains, and water mains. The figure below illustrates the terminology used in Ontario, with the critical backfill soil surrounding each type of pipe highlighted, often referred to as the structural backfill for the pipe.



As highlighted in the figure, the structural backfill is critical for pipe-soil interaction to carry the loads imposed on the pipe and should consist of high quality material and proper compaction effort. For a rigid concrete pipe, this critical zone is limited to the pipe bedding which is from the bottom of the excavated trench to the springline of the pipe due to the inherent strength and load carrying capacity of the pipe. For a flexible plastic or metal pipe, the entire soil envelope from the bottom of the excavated trench to a minimum of 0.3 m above the pipe is required to allow the pipe to transfer the loads into its surrounding soil.

Comparison of Excess Soil Generated by Pipe Structural Backfill

	Concrete Pipe	Flexible Pipe
Pipe Size	1200 mm	1200 mm
Outside Diameter	1511 mm	1374 mm
Minimum Trench Width	2.51 m	2.37 m
Structural Backfill Required	1.38 m ² /lin.m	3.24 m ² /lin.m
Soil per 100 m of pipe	138 cubic metres 241 metric tonnes 14 dump trucks	324 cubic metres 566 metric tonnes 32 dump trucks

An assessment of these two very different installation details results in a plastic or metal pipe requiring more high quality backfill material and generating more than twice as much excess soil than a concrete pipe.

Concrete Pipe Generates 18 Less Truckloads of Excess Soil per 100 m of 1200 mm Pipe



A recent example of how concrete pipe can minimize excess soil generation and the construction costs related to meeting the new MECP regulation, the City of Ottawa along with local industry National Capital Heavy Construction Association (NCHCA) started their biennial construction specifications review in the summer of 2020. The review process divides

up the City of Ottawa construction specifications and assigns working groups to each component. These working groups are comprised of City of Ottawa staff and key industry individuals. The Canadian Concrete Pipe and Precast Association (CCPPA) was asked to join the Water/Sewer Working group.

During the City of Ottawa specification review, the CCPPA proposed a change to the backfill requirement, for reinforced concrete pipe (RCP) only. The proposed change for concrete pipe installation was to allow for select native soils to be used as the cover material above the pipe springline. Currently only Granular A or Granular B required backfill for up to 300 mm above the top of the pipe for both concrete and plastic pipe. It was explained that flexible pipe systems (plastic or metal) require this embedment up to 300 mm above the top of the pipe for the flexible pipe system to have the capacity to carry the required loads. However, since concrete pipe does not rely on any structural capacity provided by the cover material above the springline, native

soils could be utilised above the springline and thereby reduce the amount of excess soils generated.

This change was adopted by the City of Ottawa and is included in the 2021 City of Ottawa Construction Specifications dated March 1, 2021.

With this continuing evolution in specifications, locally produced concrete pipe provides governments and developers with a tremendous opportunity to reduce the excess soils generated, increase the use of properly processed recycled aggregates, and itself can be 100 per cent recycled at the end of a very long service life.

Precon Supplies Lined Vaults for Twin Sanitary Sewer Upgrade in Calgary

Mark Draper, P. Eng.

Regional Solutions Lead – Conveyance and Storage,
Jacobs

Calgary, Alberta

Precast Producer: **Precon**

The project located in Calgary, Alberta, consisted of twinning the existing reinforced concrete pipe (RCP) sanitary sewer. As part of this project, a flow balancing chamber would be required to balance the flow between the existing RCP sewer and new RCP sewer.

The initial design for the chamber called for either cast-in-place or a precast concrete chamber. Given the substantial cost relating to the diversion pumping required, an accelerated construction solution was critical to keep the project both on time and on budget. A precast concrete structure was selected as it would provide the shortest construction time.

Jacobs (CH2M) worked closely with Precon's engineering team to design the chamber. It was decided that the chamber should be fabricated in two separate structures and connected together once installed on site. This would provide safe and effective transport of each of the elements as well as provide rapid assembly on site. The size of the assembled chamber was 8 m x 4.6 m x 7.3 m high.

Some design features incorporated into the chamber were:

- Chamber designed to meet CL-800 traffic loading
- Cast in HDPE liner on all chamber elements. Liner was designed to be field welded around each joint and pipe penetration to ensure proper seal
- Chamber connection details were designed by Precon



First half of lined chamber installed



Last riser installed on lined chambers

- Stainless steel flume to be installed to provide the required flow balancing. Precon worked closely with the general contractor, Standard General, to ensure that the installation of the flume would be quick and hassle free. Special care was taken to ensure that the HDPE lining of the chamber would not interfere with the flume.

One of the most challenging constraints on the projects was the need to construct a large-scale sanitary bypass. By selecting a precast solution, the required timeframe for the bypass to be operational was reduced to approximately a three week duration at a cost of approximately \$1 million. Construction of the bypass took nearly a month to get set up and operational. Standard General along with United Rentals set up 12-18 inch pumps (6 primary & 6 backup) with 3-24 inch HDPE discharge lines running approximately 400 feet to the discharge location to bypass estimated flows of 2800 l/s. Due to the size and quantity of suction points required, the existing 1500mm RCP pipe was exposed in 3 separate locations and the top half of the pipe carefully cut and removed to allow 4-18 inch suction points to be installed at each location. These pipe tops were carefully reinstalled on the existing line after the bypass was decommissioned and removed from site. This operation proved very challenging due to the congested work area within a City of Calgary park in very close proximity to Nose Creek, a feedermain as well as an active CPR rail line ROW.

Precon also worked closely with the general contractor, Standard General, to ensure each of the chamber elements were delivered sequentially as the space, on site, was limited.

Jacobs (CH2M) would like to thank Precon for their precast concrete proficiency in terms of engineering, production and logistics. Precon was able to address the challenges associated with the balancing flow chambers and ensure that a high-quality product was produced, delivered and quickly assembled on site.

CCPPA Technical Resources Manager - Alberta & British Columbia




Trevis Hanson, C.E.T.

The Canadian Concrete Pipe & Precast Association is pleased to announce that Trevis Hanson, C.E.T., has been appointed to the position of CCPPA Technical Resources Manager - Alberta & British Columbia.

Trevis graduated from Lethbridge Community College in 1995 with a diploma in Civil Engineering Technology. He has over twenty-five years of experience, including employment with consulting engineers and contractors. His most recent position was as a Bridge Operations Technologist with the City of Calgary since 2014. Prior to that, Trevis was a Sales Representative with Armtect Engineered Precast Concrete from 2012 to 2014. This position involved promoting sound wall systems and mechanically stabilized earth retaining wall systems. He currently resides in Okotoks, Alberta.

Please join us in welcoming Trevis to the Canadian Concrete Pipe & Precast Association.



Forterra Provides Microtunneling Solution for Twin Culvert Replacement

Greg MacDonald, P.Eng.

Senior Structural Engineer, Principal
Harbourside Engineering Consultants
Calgary, Alberta

Precast Producer: **Forterra Pipe & Precast, Ltd.**

Harbourside Engineering Consultants (HEC) was retained by Construction Demathieu and Bard (CDB) to develop the structural design and temporary construction works required for the Calamity Creek Culvert Replacement Project, just north of New Liskeard, Ontario. The purpose of the project was to replace and decommission an existing cast-in-place reinforced concrete, single cell box culvert having a cross section of approximately 3.05 m wide x 2.45 m high, running 270 m long. The existing structure was also situated up to 8 m below the grade of the roadway, which added to the project's challenges. Ministry of Transportation of Ontario (MTO) project specifications required twin 2.1 m inside diameter (I.D.) pipe culverts to meet the predetermined hydraulic capacity requirements. The MTO contract also required that the project be completed without causing significant disruptions to the traffic along Highway 11.

Forterra recommended that the concrete microtunneling pipe would be produced using the "drycast" process, which allows for higher production rates compared to the "wetcast" process. It was designed with a typical microtunneling joint consisting of a 13 mm thick galvanized steel ring. In addition to the steel end ring, the joint also featured a confined tapered profile gasket that provides a hydrostatic capacity of 30 psi. Forterra's engineering team provided the structural designs for the pipe which were reviewed and accepted by Harbourside Engineering and the MTO.



Aerial view of Highway 11 project



Launch shaft for microtunneling pipe

The 2.1 m microtunneling pipe also needed to meet several quality assurance and certification standards, including the requirements of the Canadian Precast Concrete Quality Assurance (CPCQA) certification program. Pipe segments were also assessed using the requirements of the D-Load test and hydrostatic test, which were performed by Forterra at their manufacturing facility. The D-Load (or Three Edge Bearing test - 3EB) is a physical test used to ensure the pipe will provide the required structural capacity.

The tunneling contractor that was selected for this project was CRS Tunnelling. They selected an Earth Pressure Balance Tunnel Boring Machine (EPBTBM) for this project. The EPB allows soft, wet, or unstable ground to be tunneled safely with speed. This TBM was equipped with face control doors and chamber access in case the crew needed to go into the cutting head chamber for maintenance or inspection. The latter would prove important as the TBM did hit a major underground obstacle of wood debris during the first drive.

The twin pipe culverts were installed in two drives. Each drive would run the entire 270 m length. As mentioned above, the project did encounter a delay due to the debris, during the first drive but was able to finish. The delay resulted in the second drive occurring during a cold spell with some morning temperatures hitting -40°C. Both the concrete microtunneling pipe and the TBM continued to operate throughout this very cold temperature. The second drive broke through the receiving shaft on December 12, 2019. The project, which included the decommissioning of the existing culvert, was completed in October 2020.

Forterra's concrete pipe/precast engineering expertise was a key part of this project's success. Their contribution in terms of design and production of the microtunneling pipe solution along with their collaboration throughout the project exceeded expectations.

Stanley Park's Beaver Lake Utilises Custom Box Culverts with Fish Ladders to Improve Ecosystem

Jason Omelianiec

Technical Marketer

Precast Producer: **Langley Concrete Group**

The iconic 405-acre Stanley Park borders downtown Vancouver, British Columbia, and sits pristinely on Burrard Inlet offering visitors a unique glimpse at what the natural setting of Vancouver looked like before urbanization. Nestled inside Stanley Park is Beaver Lake, which is one of the very few freshwater lakes existing in Vancouver, and the outlet Beaver Creek is one of only three remaining riparian waterways in the city of Vancouver.

The Beaver Lake Restoration Plan includes an effort to improve the ecosystem of the lake, and in Phase 1 the use of precast concrete Box Culverts with fish ladders and custom Headwalls to upgrade the lake's outlet stream was conceived. By improving the flow of freshwater to Burrard Inlet and thereby enhancing the channel characteristics of the outlet, it is hoped that many native species will be encouraged to pass through and thereby populate the lake.

Precast concrete box culverts supplied by the Langley Concrete Group, which are designed in accordance with ASTM C1433M specifications, were selected with inside spans of 3.35 m and internal rise of 1.52 m

and in lengths of 2 m weighing 17,560 kilograms each. In each of the five sections, variable-height custom fish ladders with staggered rectangular low-flow notches were cast at the invert of the precast box culverts. Pooling waters flowing between the seven fish ladders should facilitate

the necessary water for fish to pass the vertical incline from Burrard Inlet to Beaver Lake. At each end of the run of precast concrete box culverts, Langley Concrete Group also supplied 4.1 m span headwalls for both inlet and outlet control structures.

Jack Tupper, Landscape Architect - Park Development (City of Vancouver) provided a project write-up. The following is an excerpt from his report:

"In the fall of 2020, as part of the Beaver Lake Enhancement Masterplan, the City of Vancouver worked with a team of consultants and contractors to install Phase 1 of the project; a newly improved Beaver Lake Outlet.

"With dramatic fluctuations in water levels, this new larger and more robust outlet is able to balance lake levels throughout the year and provide continuous flow into the adjacent Beaver Creek. Even the growing population of beavers, that inhabit the appropriately named lake, struggle to block the new structure entirely.

The new outlet is the first step in rejuvenating Beaver Lake and its ecological health."



Completed structure



Proform Utilises 3D Modeling, of a large box culvert project, for a New Residential Development in the City of Calgary

Brock Dyck, P.Eng.
 Project Engineer
 Urban Systems Ltd.
 General Contractor: **Blue-Con**
 Precast Producer: **Proform**

With communities seeing more and more surface flooding due to larger intensity storms and inadequate underground infrastructure, the City of Calgary is being proactive in mitigating flood waters in new upcoming communities. Anticipating flooding at the design stage not only adds future savings to homeowners but also has a big positive environmental impact on future communities.

Springbank Hill Phase 3 is one of these new communities to undergo large scale storm retention at the design and construction stage to mitigate future flooding and the need to upgrade existing underground infrastructure in the future, thus saving costs and negative environmental impact.



Maintenance hole and culvert connection

In order to maintain the community layout and clearances to sanitary and other services, the storm sewer lines were placed in the middle of a winding road. This resulted in the requirement of having a 1200 mm x 2400 mm precast concrete box storm water retention line to follow the “S” curve shape of the road.

In conjunction with Blue-Con (the general contractor), Proform’s engineering team produced a 3D model showing the location of each of the 100 precast box units that would be providing the stormwater retention system. In addition, this model was used to determine the location of each of the maintenance holes, ensuring that they would not be located between two ends of a box unit and providing the

most effective use of each precast box unit. There were also a number of beveled, reinforced concrete pipes (1050 mm inside diameter) included in this storm sewer system.

Logistical coordination was also enhanced by the 3D model. The large majority of the box units were beveled to produce the required curvature and ensure that they would follow the roadway centerline. The 3D model was used to colour-code each of the boxes belonging to their appropriate radius and confirm that the proper beveled box was installed in the proper location and radius.

Given the high production demands, Proform was able to produce these box structures using the “dry cast” method which allows for higher production than the wet cast.

Approximately four to six boxes were produced per day. Using the modeling, Urban Systems, Blue-Con and Proform were able to coordinate production and ensure that the required boxes were produced and delivered to the site without causing unnecessary delays. This was key to ensuring that the project remained on schedule and in line with the design requirements.

I would like to thank both Blue-Con and Proform for their contribution to the success of this project, and highlight that a significant amount of effort was put into the design stage of this project with Urban Systems, Blue-Con and Proform working together. Through this early collaboration, we were able to identify and address a number of issues prior to the installation phase of the project to make this a successful project for generations to come.



Box culvert designed and manufactured with a required radius

info@langleyconcretegroup.com
 sales@langleyconcretegroup.com

THE Langley Concrete Group
 The Langley Concrete Group of Companies

FOLLOW US!
 in

CONCRETE PIPE BOX CULVERTS MANHOLES CATCH BASINS CUSTOM PRECAST	STORMWATER TREATMENT HYDRO/TEL VAULTS CHAMBERS/METER BOXES HEADWALLS	STONE STRONG WALL SYSTEM LIGHT POLE BASES LINED PRECAST PRODUCTS MICROTUNNELING PIPE
---	---	---

PHONE: 604-533-1656
TOLL FREE: 1-800-667-9600

LOMBARD PRECAST INC. LANGLEY CONCRETE AND TILE LTD.
 4315 HILLBANK ROAD DUNCAN, BC V9L6L8 20142 LOGAN AVE LANGLEY, BC V3A 4L5
 Ph 250.478.9581 Fax 250.478.0353 Ph 604.533.1656 Fax 604.533.8191

Global Leaders in Precast

NEW HAMPTON **Hawkeye Pedershaab**
 Metal Fab **ESPECIALTIES IN PRECAST CONCRETE**

BFS

<p>New Hampton Metal Fab 928 West Milwaukee New Hampton, Iowa 50659 USA Phone: +1 (641) 394-4111 Telefax: +1 (641) 394-4542 www.nhmfcorp.com</p>	<p>HawkeyePedershaab + BFS 506 S. Wapello Street Mediapolis, Iowa 52637 USA Phone: +1 (319) 394-3197 Telefax: +1 (319) 394-3977 www.hpct.com www.bfs-casagrande.de</p>
--	---

GCI Groups

GCI PIPE PRODUCTS INC.

GCI have been manufacturing for over 25 years and is successful in designing machine concepts in advance that enable efficient and cost-effective everyday production.

GCI PIPE PRODUCTS INC.
 PHONE 418-654-6569
 www.gcipipe.com

PIERRE RANCOURT
 SALES MANAGER CANADA

CONCEPT | DESIGN | SOLUTIONS

BUILDING SUSTAINABLE PRECAST CONCRETE INFRASTRUCTURE.

M CON
 PIPE & PRODUCTS INC
WWW.MCONPIPE.COM
1 866 537 3338

SERVING CENTRAL, SOUTHWESTERN AND NORTHERN ONTARIO

Engineered Pipe & Precast Solutions

UTILIZING THE BEST FEATURES OF CONCRETE AND STEEL

ENGINEERED AND MANUFACTURED TO MEET YOUR EXACT SPECIFICATIONS

24/7 SUPPORT FROM DECAST'S EXPERT FIELD SERVICES TEAM

DECAST
 Leading Infrastructure Solutions

T 705.734.2892 8807 County Road 56
 TF 800.461.5632 Utopia, ON L0M 1T0
 F 705.734.2920 decastltd.com



Cast in Collaboration

Russell Sleeper
Project Coordinator
TULLOCH
Precast Producer: **DECAST**

“TULLOCH understood the need to collaborate early,” says Dan Haggerty of DECAST.

“I received the initial call from John McDonald. He knew that consulting with those who would build and install the components would make the design and project planning processes efficient. And it ensured his design would consider all the challenges associated with this complex project.”

So began the Fort Creek Aqueduct Replacement project in Sault Ste. Marie, Ontario, with tight collaboration as the foundation for a complex, time-sensitive project in a busy commercial corridor.

Sault Ste. Marie’s Fort Creek watershed has a total catchment area of 1,516 hectares. It runs approximately 8 km to its outlet south of Bay Street West. A flood control dam intercepts run-off from the watershed; and the aqueduct channels it through a heavily urbanized area, known as Steelton, south to St. Mary’s River.

TULLOCH Engineering Inc. had completed a Class Environmental Assessment for the City of Sault Ste. Marie, to determine the hydraulic capacity required of a replacement aqueduct to meet current stormwater standards. Its hydrologic analysis of the watershed determined that the aqueduct must be designed to accommodate the highest flows generated by the Timmins Regional Storm.

Parts of the original structure, a cast-in-place concrete box storm sewer, were over one hundred years old and required replacement to ensure the safety of motorists and pedestrians. The City of Sault Ste. Marie engaged TULLOCH again to undertake detailed design and tendering for construction.

The project divided naturally into two phases based on scope and challenges. Phase 1 replaced a significant length of aqueduct under Wellington Street West, one of the main roads bringing traffic into the city. Phase 2 solved the specific challenge of replacing an aged box culvert running beneath a narrow laneway road with several utilities overhead.



Hydraulic lift for open bottom culvert installation

Wellington Street, sections were tailored. Some sections included lateral pipe connections to carry water from the old to the new aqueduct, thereby allowing the old structure to be abandoned in phases and would switch the flow between barrels of the twin cell closed box section. Where possible, sections were made wider to maximize the size of the opening. These meticulous design details optimized the hydraulic performance of the aqueduct. They required TULLOCH to collaborate continually during the design process; from DECAST’s constructability assessments and tight dimensional tolerances for precasting, to the exacting installation by Avery Construction. The benefits to Sault Ste. Marie were clear at the end of Phase 1: a critical infrastructure project completed safely, with minimal impact to traffic and significant budgetary savings.

Phase 2 presented more complexity, yet again, the TULLOCH-DECAST-Avery collaboration found smart solutions. TULLOCH’s John McDonald described the challenge:

“Part of the existing aqueduct was a cast-in-place box culvert from the early 1900s. Its lid formed the road surface for a laneway parallel to John Street. It had failed a few times and become a burden on city maintenance and a public safety hazard.”

Property limits in the laneway approached the edge of the old aqueduct, leaving the team with little space to work in. A web of overhead utilities

and an irregular shape through the cross-section compounded the challenge. The team looked at liner options during TULLOCH’s design but the shape, hydraulic and structural concerns demanded a robust structural solution with sufficient hydraulic capacity. TULLOCH and DECAST devised a three-sided precast culvert that would sit on new footings within the existing structure. While avoiding demolition and removal of the old culvert, the solution left a restrictive area that would determine the size of new precast items. The structural design called for 45 MPa concrete to achieve thinner precast walls and an interior shape to accommodate maximum stormwater volumes. Each section would then slide into place with only 50 mm of buffer space at its sides and 25 mm above. Avery Construction’s custom hydraulic cart answered the challenge of lifting the precast sections 25 mm above the foundation’s keyway, moving the sections along the aqueduct line, and then lowering them into place.

The team designed and constructed 95 per cent of the Phase 2 structure this way. The remainder, where the aqueduct crossed John Street, benefited from extra space. It allowed

a full demolition of the existing structure. The replacement precast sections were tied into a secondary bypass aqueduct, twinning the overflow structures in the middle of the street.

Precast was undoubtedly the right choice for this project, however, its design was just one of several collaborative initiatives that combined to deliver an exceptional piece of infrastructure for the City of Sault Ste. Marie. Open communication in design, manufacture and installation were crucial. The team shared its expertise freely and all partners clearly took a conscientious approach to service, contributing to early completion within agreed budgets.



Fort Creek Aqueduct project aerial view

Safety, time and space were key considerations for both phases. Phase 1 had to be implemented with two of Wellington Street’s four lanes always open for traffic. Sanitary laterals beneath the existing aqueduct also had to be replaced without interrupting sanitary and water services. The key project challenges suggested that a precast solution would be the best option. The tendering process created a credentialed team to execute it, bringing together TULLOCH, DECAST Ltd., and Avery Construction Ltd.

The team designed standard, 2.44-metre-long precast box sections to be installed beside the existing aqueduct. At various points along

Retirement Announcement: Grant Fraser



Grant Fraser

After entering his 48th year of extraordinary service in the steel and wire reinforcing industry, Grant Fraser announced his retirement as of April 2, 2021. Grant held various positions at Stelco, Frost Fence, LEC Steel, Laurel-LEC Steel and most recently at Nucor-Laurel Steel.

Grant was also a very active member of multiple trade associations including the OCPA and CCPA. His contributions were always focused on improving the industry.

Although Grant has retired from day-to-day work life to spend time with family and riding his road bike, he will continue to provide consulting support to the Nucor-Laurel Steel team.

Please join us in congratulating Grant on his distinguished career, contributions and accomplishments.

Retirement Announcement: Bernard Grégoire



Bernard Grégoire

Bernard Grégoire, President and COO of Hamilton Kent, had announced his retirement as of May 2021.

Bernard dedicated his entire career to serving the manufacturing industry. With a background in engineering, he always searched for creative and innovative solutions. As stated by Bernard, "During my twenty-six year tenure, I feel as though Hamilton Kent has made significant contributions to enhancing the resiliency of underground infrastructure by providing innovative and reliable watertight seals."

During his time at Hamilton Kent, Bernard was responsible for two acquisitions: IPS in 2006 and NC Rubber in 2001. Additionally, Bernard expanded Hamilton Kent's manufacturing base with the commissioning of a new manufacturing facility in Winchester, Tennessee in 2007.

Please join us in congratulating Bernard on his prominent leadership role during his career, as well as his various contributions to our industry.

The world needs concrete solutions



Providing a more resilient infrastructure... That's our job.

OCEAN Pipe
HEIDELBERGCEMENT Group

INLAND Pipe
HEIDELBERGCEMENT Group

Vancouver
604 269 6700

Calgary
403 279 5531

Edmonton
780 448 1351

Winnipeg
204 334 4300



Building Foundations for Communities across Saskatchewan

www.sviprecast.com
306-842-5854



M CON
PRODUCTS INC
mconproducts.com



**LEADERS IN PRECAST
CONCRETE INFRASTRUCTURE
PRODUCTS SINCE 1989.**

Proudly serving Eastern,
Central and Northern Ontario.



PART OF THE PRECAST GROUP OF COMPANIES. Visit ThePrecastGroup.com

PROFORM
CONSTRUCTION PRODUCTS

Your One Stop Shop for
Precast & Construction Needs
in Western Canada

WWW.PROFORM.CA | 800-859-5541 | INFO@PROFORM.CA



RED DEER PLANT
403-343-8000

CALGARY PLANT
403-261-3851

HEAD OFFICE
403-343-6099



**Superiority
is a beautiful thing.**

You've designed the structure. You've stamped the plans. And yes, you've assumed the liability. So think twice about specifying flexible drainage pipes. Because when you spec flexible a structure has to be built around the pipe. With Forterra reinforced concrete pipe, you buy a structure. Durability. Peace of mind. Not to mention, engineering advice and technical support from experts who have the knowledge to get it right. And that's a beautiful thing.

FORTERRA
GROUNDED IN STRENGTH



Download our free ebook, *Top 10 Reasons to Specify Concrete Pipe*, at forterrabp.com/topten.

forterrabp.com

The pipe that will revolutionize
the landscape of infrastructure systems
is here, and it's PERFECT.



concastpipe.com | 1 800 668 PIPE | sales@concastpipe.com

CON CAST PIPE

COLDSTREAM
CONCRETE

THE LEADER IN CUSTOM HEAVY PRECAST CONCRETE ELEMENTS



coldstreamconcrete.com | 519.666.0604

business pipeline

Concrete Pipe/Drainage Products Producer

Coldstream Concrete Limited
 Location: Ilderton, ON
 Tel: 519-666-0604
 Fax: 519-666-0977
 Email: rsbrown@coldstreamconcrete.com
 Website: www.coldstreamconcrete.com
 Contact: Robert Brown

Con Cast Pipe
 Location: Puslinch, ON
 Tel: 519-763-8655
 Email: sales@concastpipe.com
 Website: www.concastpipe.com
 Contact: Jason Spencer or Mark Eaton

DECAST Ltd.
 Location: Barrie, ON
 Tel: 1-800-461-5632
 Fax: 705-734-2920
 Email: jtully@decastltd.com
 Website: www.decastltd.com
 Contact: Jim Tully

Forterra Pipe and Precast
 Locations: Whitby, Cambridge, Ottawa
 Tel: 1-888-888-3222
 Fax: 519-621-8233
 Email: Shane.Egan@forterrabp.com
 Website: www.forterrabp.com
 Contact: Shane Egan

Inland Pipe/Ocean Pipe
 Locations: Calgary, Edmonton, Regina, Winnipeg, Vancouver
 Tel: 1-800-268-0785
 Fax: 403-261-6751
 Tech Inquiries: Justin Arnott
 Email: Justin.Arnott@LehighHanson.com
 Website: www.inlandpipe.com

LafargeHolcim
 Locations: Calgary, Edmonton, Winnipeg, Saskatoon, Thunder Bay
 Tel: 780-479-5232
 Fax: 780-410-3699
 Email: ryan.finlay@lafargeholcim.com
 Website: www.lafarge.ca
 Contact: Ryan Finlay

Langley Concrete Group
 Locations: Langley, Victoria & Chilliwack, BC
 Tel: 604-533-1656
 Fax: 604-533-8191
 Email: pipeman@langleyconcretegroup.com
 Website: www.langleyconcretegroup.com
 Contact: Mark Omelianiec

M CON Products Inc.
 Location: Carp, ON
 Tel: 1-800-267-5515
 Email: info@mconproducts.com
 Website: www.mconproducts.com
 Contact: Marco Mion

M CON Pipe & Products Inc.
 Location: Ayr, ON
 Tel: 519-632-9112
 Fax: 519-632-7440
 Email: msabine@mconpipe.com
 Contact: Mark Sabine

Proform Construction Products
 Locations: Edmonton, Red Deer & Calgary, AB
 Toll Free: 800.859.5541
 Email: info@proform.ca
 Website: www.proform.ca
 Contact: Rob Heemsker or Syd Stansall

Rainbow Concrete Industries Ltd.
 Locations: Sudbury, ON
 Tel: 1-800-461-6281
 Fax: 705-566-4813
 Email: sales@rcil.ca
 Website: www.rcil.com
 Contact: Boris Naneff

Souris Valley Industries
 Locations: Weyburn, SK
 Tel: 306-842-5854
 Fax: 306-842-1011
 Email: dustin@sviprecast.com
 Website: www.sviprecast.com
 Contact: Dustin Bell

Gaskets and Connectors

Hamilton Kent
 Location: Etobicoke, ON
 Tel: 1-800-268-8479
 Fax: 416-674-6960
 Email: bernard.gregoire@hamiltonkent.com
 Website: www.hamiltonkent.com
 Contact: Bernard Gregoire

Press-Seal Corporation
 Location: Fort Wayne, IN
 Toll-free: 800-348-7325
 Cell: 617-803-1750
 Email: mtomkinson@press-seal.com
 Website: www.press-seal.com
 Contact: Matt Tomkinson

Reinforcing Steel

Laurel Steel
 A Division of Harris Steel ULC
 Location: Burlington, Ontario
 Tel: 800-265-6811
 Fax: 905-634-7888
 Email: grant.fraser@laurelsteel.com
 Website: www.laurelsteel.com
 Contact: Grant Fraser

Numesh Inc.
 Location: Laval, PQ
 Tel: 1-800-363-0847
 Fax: 450-663-9049
 Email: john.nesbitt@numesh.com
 Website: www.numesh.com
 Contact: John Nesbitt

StelCrete Industries Limited
 Location: Niagara Falls, ON
 Tel: 1-866-924-0837
 Fax: 905-735-3955
 Email: bhansen@stelcrete.com
 Website: www.stelcrete.com
 Contact: Bob Hansen

Precast Manufacturing Equipment and Accessories

GCI Pipe Products Inc.
 Québec, QC
 Tel: 418-654-6569
 Email: p.rancourt@gcipipeproducts.com
 Website: www.gcigroups.com
 Contact: Pierre Rancour

HawkeyePedershaab
 Location: Mediapolis, IA
 Tel: 800-626-1453
 e-mail: rbeelman@hawkeyepedershaab.com
 website: www.hawkeyepedershaab.com
 Contact: Randy Beelman

Mel C. Marshall Industrial Consultants Inc.
 Location: Delta, BC
 Tel: 604-943-8512
 Fax: 604-943-2738
 Email: mel@mcmconsultants.ca
 Website: www.precastconcretebc.com
 Contact: Mel Marshall or Braden Marshall

LAFARGE
 Building better cities™

Providing Precast Solutions to
 Underground Infrastructure in Western Canada

www.lafarge-na.com/pipe

PROUDLY PRODUCING QUALITY CONCRETE PRODUCTS FOR OVER HALF A CENTURY

OUR WIDE RANGE OF PRODUCTS INCLUDE:

- ▶ Concrete Pipe & Box Sections
- ▶ Maintenance Holes & Catchbasins
- ▶ Ready Mix Concrete
- ▶ Standard & Architectural Blocks
- ▶ Architectural Stone, Blocks & Bricks
- ▶ Landscaping Products
- ▶ Septic Tanks & Accessories
- ▶ Precast Concrete
- ▶ Packaged Materials
- ▶ Electrical Structures
- ▶ Construction Accessories
- ▶ Mining Products
- ▶ Prestressed Hollowcore Slabs
- ▶ Architectural Precast
- ▶ Custom Precast

2477 Maley Drive, Sudbury, ON P3A 4R7
 Ph:705-566-1740 1-800-461-6281 Fax:705-566-4813
www.rcil.com



NUMESH

PRODUCTS

- COILS
- PIPE MESH
- ENGINEERED MESH
- STRAIGHT & CUT WIRE
- TUNNEL MESH & LADDERS

1 800 363-0847 | NUMESH.COM

SERVICE WITH A SMILE
 ONLY MEANS SOMETHING
 IF THE CUSTOMER IS ALSO SMILING.

Laurel Steel
 A DIVISION OF HARRIS STEEL ULC

BURLINGTON, ONTARIO
 1-800-265-6811
www.laurelsteel.com

Your reinforcing depot for
 PRECAST - MINING - CONSTRUCTION
 ISO 90001 ISO14001

Quality ...products and service
Service ...long-term
Value ...reduced costs

Our pipeline is open.
 Contact us now to explore a better way
 to help your clients with their projects.

StelCrete Industries Limited
 P.O. Box 837
 7771 Stanley Avenue
 Niagara Falls, ON Canada L2E 6V6

t: 905.354.5691 / 1.800.263.7110
 f: 905.356.1679
info@stelcrete.com



www.stelcrete.com
 manufacturers of pre-welded reinforcement and structural hardware.